## राष्ट्रीय आयुर्वेद संस्थान

मानद विश्वविद्यालय (डी-नोवो), जयपुर

क्रमांक एफ. 4(64) / सम्पदा / 2023 / 1645 न

दिनांक : 06.09.23

## अल्पकालीन निविदा

संस्थान केन्द्रीय प्रयोगशाला के कॉल्ड स्टोरेज कक्ष का सम्पूर्ण रिपेयर / रेनोवेशन का कार्य निम्नलिखित विवरण अनुसार अल्पकालीन निविदाओं के माध्यम से करवाया जाना है, इच्छुक फर्म साईट का निरिक्षण कर अपनी निविदाए दिनांक 08.09.2023 को मध्यान 12:30 बजे तक सीलबन्द लिफाफे पर उक्त निविदा का नाम लिखकर संस्थान में कुलपित महोदय को प्रेषित करे। कार्य का विवरण निम्नप्रकार है :--

S.N	Description of Work	Qty.	Rate per unit	Amount
1	Dismantling tile work in floors and roofs laid in cement mortar including stacking material within 50 metres lead.			
1.1	For thickness of tiles 10 mm to 25 mm	03 Sqm		
2	Repairs to plaster of thickness 12 mm to 20 mm in patches of area 2.5 sq.meters and under, including cutting the patch in proper shape, raking out joints and preparing and plastering the surface of the walls complete, including disposal of rubbish to the dumping ground, all complete as per direction of Engineer-in-Charge.	·		
2.1	With cement mortar 1:4 (1 cement : 4 fine sand)	12 Sqm		
3	Providing and fixing Ist quality ceramic glazed wall tiles conforming to IS: 15622 (thickness to be specified by the manufacturer), of approved make, in all colours, shades except burgundy, bottle green, black of any size as approved by Engineer-in-Charge, in skirting, risers of steps and dados, over 12 mm thick bed of cement mortar 1:3 (1 cement : 3 coarse sand) and jointing with grey cement slurry @ 3.3kg per sqm, including pointing in white cement mixed with pigment of matching shade complete.	53 Sqm		
4	Removing white or colour wash by scrapping and sand papering and preparing the surface smooth including necessary repairs to scratches etc. complete	20 Sqm		
5	Providing and applying white cement based putty of average thickness 1 mm, of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth complete	28 Sqm	2	*
6	Distempering with oil bound washable distemper of approved brand and manufacture to give an even shade:			
6.1	New work (two or more coats) over and including water thinnable priming coat with cement primer	25 Sqm		
7	New work (two or more coats) over and including water thinnable priming coat with cement primer			
7.1	Two or more coats on new work	70 Sqm		
8	Providing and fixing 18 mm thick gang saw cut, mirror polished, premoulded and prepolished, machine cut for kitchen platforms, vanity counters, window sills, facias and similar locations of required size, approved shade, colour and texture laid over 20 mm thick base cement mortar 1:4 (1 cement : 4 coarse sand), joints treated with white cement, mixed with matching pigment, epoxy touch ups, including rubbing, curing, moulding and polishing to edges to give high gloss finish etc. complete at all levels			
8.1	Granite stone slab colour black, Cherry/Ruby red Area of slab over 0.50 sqm	1.7 Sqm		
	Total Rupees  GST			

- 1. फर्म को कार्य का भुगतान कार्य सन्तोषप्रद होने पर किया जायेगा।
- 2. फर्म को उपरोक्त विवरणानुसार ही कोटेशन भर कर प्रस्तुत करना होगा।
- 3. फर्म द्वारा कोटेशन के साथ GST का प्रमाण पत्र संलग्न करना अनिवार्य है।
- 4. कार्य पूर्ण होने पर बिल 02 प्रतियों में सम्पदा विभाग में प्रस्तुत करना होगा जिससे भुगतान की कार्यवाही की जा सके।

उप निदेशक (प्रशासन)

प्रतिलिपि:- सूचनार्थ हेतु प्रेषित।

भाः प्रतिष्ठापन शांखा को दी जाकर लेख है दिनांक 08.09.2023 को मध्यांन 12:30 बजे तक उक्त कार्य की निविद्या प्राप्त कर सम्पदा विभाग में भिजवाये जाने की व्यवस्था करावें।

उप निदेशक (प्रशासन)